

# Addendum No. 3 March 29, 2023

## WSU Sunrise Orchard Irrigation Line and Pond

Washington State University Wenatchee, WA

Project No. 1262-2020 Washington State University Facilities Services, Capital

### Addendum No. 3 3/29/2023

### WSU Sunrise Orchard Irrigation Line and Pond Washington State University Wenatchee, WA

Bid Date: April 5, 2023

- 1. This Addendum forms a part of the Contract Documents and modifies the original Bidding Documents dated February 9, 2023, and any prior addenda, as noted below.
- 2. Please acknowledge receipt of this addendum on the Form of Proposal.

This Addendum consists of two total pages and no attachments.

#### **Changes to prior Addenda:**

None

#### **Changes to Bidding Requirements:**

None

#### **Changes to Specifications:**

None

#### **Bidder Questions:**

Q 1. Is the earthwork volume of cut/fill supposed to balance for the proposed sitework, relative to the pond/berm construction? Can the engineer provide approx quantities?

WSU Response: The site as it is currently has excess cut for the installation of the pond. We estimate approximately 6130 CY of Cut and 4030 CY of Fill for the construction of the pond and berms to finish grade. The liner will require 6" of CSBC below finish grade, estimated to approximately 1370 CY to cover the pond and berm. This leaves an excess Net Cut of 3470 CY that will need to be duffed on site near the pond.

Q 2. Per the "Berm Construction Detail" on Sheet C-950; are the bidding contractors to assume that the Engineer's intent is to install a 7.5' wide keyway throughout the entire footprint of the new "Top of Berm"?(i.e. Will the keyway be required throughout the entire footprint of the berm?)

WSU Response: This is correct.

END OF ADDENDUM No. 3